





ADDENDUM NO. 01

Series of 2025

This Addendum No. 01 is issued to modify or amend items in the Bidding Documents for the Provision of Capital Outlay - Office Equipment (Air Conditioner) for the Operation of the New Admin Building, Library, University Gymnasium, CEGS, Kinaadman Hall Auditorium and School of Medicine. This shall form an integral part of the Bid Documents.

Name of Project: Provision of Capital Outlay - Office Equipment (Air

Conditioner) for the Operation of the New Admin Building, Library, University Gymnasium, CEGS, Kinaadman Hall

Auditorium and School of Medicine

Location: CSU Campus, Ampayon, Butuan City

Brief Description: Provision of Air Conditioner for various offices

Approved Budget

for the Contract : **Php.** ₱6,229,000.00

Source of Funds: RAF - MC Higher Education Program FY 2025

Contract Duration: 60 Calendar Days

Procurement Scheme: Lot

Please be informed of the changes in the Bidding Documents as follows:

	CHANGES/ AMENDMENT ITEM & DESCRIPTION					
NO.		QTY	UNIT	TOTAL COST		
	AIRCONDITIONER					
1.	6 HP - 52,500 kJ/hour Power Input - 5,300 W Physical Indoor Unit Net Weight - 62.5 kg Indoor Unit (w -580 x h-18750 x d-525) in mm Indoor Unit Packing (w-670 x h-1870 x d-525) in mm Outdoor Unit Net Weight -95 kg Outdoor Unit (w-936 x h-722 x d-336) in mm Refrigerant (Type/kg -R410A) Piping Liquid / Gas Side (9.52/19.1 mm) Max Refrigerant Pipe Length - 50 Power Supply (V-230, Ph-1 or Ph - 3, Hz -60) Indoor Noise Level-Hi/Mi/Lo(db/a) -58/54/52 Inverter type Additional Specs: Self-Diagnostic Free Installation Free extra 20 ft copper tube with accessories 1 year warranty With service center QTY: 8 UNIT: UNIT	1	LOT	₱6,229,000.00		
	2 HP Aircon Type: floor stand, inverter Capacity: 3 TR Warranty: at least 1 year warranty (parts and services). 5 years compressor warranty With free installation and 10ft copper tubing with bracket QTY: 27 UNIT: UNIT 3 HP Aircon Type: floor stand, inverter Capacityr: 3 tons. Warranty: at least 1 year warranty (parts and services).					







•	TOTAL AMOU	JNT ₱ 6,229,000.00
QTY: 10 UNIT: UNIT		
1 Year Warranty		
H)1750 mm		
Caster wheels with lock Dimensions: (L)910 x (W)480 x		
Automatic vertical louver and Manual horizontal louver •		
control • Auto shut-off water pump with low water alarm •		
rirus/bacteria & sterilize the surrounding air • With remote		
Continuous water supply inlet • With UV Light to eliminate		
adjust mode and wind mode • With temperature display •		
screen LCD control panel • With Automatic temperature		
9 levels wind speed setting • 40 liters water tank capacity 64dB Lowest Noise • With 1-8 hours timer • With Touch-		
3 sides cooling pad with dust proof net • 9,000 m³/h Airflow		
115 watts power for 65 sqm. area		
ndustrial Air Cooler		
QTY: 2 UNIT: UNIT		
Controller, Ceiling Mount, Heavy Duty		
13 Ft Diameter Fan Blade HVLS Fan, 230v, 60hz, With		
HVLS Fan		
QTY: 2 UNIT: UNIT		
Vith free installation and 10ft copper tubing with bracket		

For guidance and information of all concerned.

MICHELLE JAPITANA, D. Eng. Chairperson, Bids and Awards Committee JAPITANA, D. Eng.