



ADDENDUM NO. 01 Series of 2022

This Addendum No. 01 is issued to modify or amend items in the Bidding Documents for the **Provision of Transformers for CEGS Building, CCIS Building, and CEIT Annex Building**. This shall form an integral part of the Bid Documents.

Name of Project: **Provision of Transformers for CEGS Building, CCIS Building, and CEIT Annex Building**
Location: CSU Campus, Ampayon, Butuan City
Brief Description: Provision of Transformers for CEGS Building, CCIS Building, and CEIT Annex Building
Approved Budget for the Contract : **Php. 2,146,331.25**
Source of Funds: IGF 2022
Contract Duration: 45 Calendar Days

Please be informed of the changes in the Bidding Documents as follows:

CHANGES/ AMENDMENT		
TECHNICAL SPECIFICATION		
	FROM	TO
	Contract Duration: 60 Calendar Days	Contract Duration: 45 Calendar Days
ITEM No.	DESCRIPTION	
1.	Transformers 3 units 333KVA Distribution Type Transformer Brand New 13.2KV / 7620 V Primary 240V/120V Secondary -(Includes the delivery, hang-up, and banking of transformers, provision of the hardware accessories: cut-out fuses, lightning arrester, connector lugs, transformer connecting cables – 250mm ² , THW, and other related items) -(Unit Price Includes Labor and Installation) The item shall consist of all labor, materials, tools, and equipment necessary to install electrical wiring, piping, and fixtures and all appurtenant work in accordance with the work shown on the plan and in accordance with the standard specification. -1 year warranty Inclusion: - Permit Processing - Shall have PCAB License specializing in electrical installation - pull down of existing 3 units 75KVA distribution transformers	Transformers 3 units 333KVA Distribution Type Transformer Brand New 13.2KV / 7620 V Primary (Y Connection) 240V/120V Secondary (Delta) Copper Primary and Secondary Winding -(Includes the delivery, hang-up, and banking of transformers, provision of the hardware accessories: cut-out fuses, lightning arrester, connector lugs, transformer connecting cables – 250mm ² , THW Copper wire, and other related items) -(Unit Price Includes Labor and Installation) The item shall consist of all labor, materials, tools, and equipment necessary to install electrical wiring, piping, and fixtures and all appurtenant work in accordance with the work shown on the plan and in accordance with the standard specification. -1 year warranty Inclusion: - Permit Processing (Occupancy Permit & Electrical Permit) - Shall have PCAB License specializing in electrical installation



Republic of the Philippines
CARAGA STATE UNIVERSITY
Ampayon, Butuan City 8600, Philippines

Competence **S**ervice **U**prightness

Phone: 09175030963
(+6385) 341-2296

URL: <http://www.carsu.edu.ph>
Email: csu.bacsecretariat@carsu.edu.ph



BIDS AND AWARDS COMMITTEE (BAC)

		<ul style="list-style-type: none">- pull down of existing 3 units 75KVA distribution transformers- Test Results shall be provided to client after the testing and commissioning
--	--	--

For guidance and information of all concerned.

ARMIE LEILA M. MORDENO, DPA, CSEE
BAC Chairperson